10	Supplying and drawing 3 core PVC Sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS: 8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 volts 4 sqmm of 56 strands 0.3mm dia Complete as per Specification.	Mtr	1300.00	159.50	Rupees One Hundred Fifty Nine and Fifty Paise Only
11	Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc,. completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above 6.50 HP to 15.00 HP with star delta starter (MR) Complete as per Specification.	no	2.00	10000.00	Rupees Ten Thousand Only
12	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm Complete as per Specification.	Sqm Cm	44000.00	0.33	Thirty Three Paise Only
13	Providing & Fixing of clamps set and borewell cap to the pump (MR)	No's	2.00	690.00	Rupees Six Hundred Ninety Only
14	Supplying & delivery of brand new best make non return valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark (50mm Gate wheel Valve. Complete as per Specification.	No's	4.00	1600.00	Rupees One Thousand Six Hundred Only
15	Supplying and delivery of brand new best make Gate Valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark . 50mm Gate Valve for distributer pipeline. 50mm dia Complete as per Specification.	No's	4.00	1145.00	Rupees One Thousand One Hundred Forty Five Only
16	Providing and fixing of 50mm GI bend to motor Complete as per Specification.	No's	4.00	219.00	Rupees Two Hundred Nineteen Only

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP, Bangalore

Executive Engineer